



### **110 Applebee Street - Contributing**

At this location is a two-story, side gabled Dutch Colonial influenced Folk dwelling built ca. 1910. The house has a rusticated concrete block foundation, a side gambrel roof of asphalt shingles, an interior brick flue and an exterior of aluminum siding. On the main (E) façade is an full-width porch enclosed ca. 1970 with aluminum siding, a triple set of one-over-one vinyl windows and wood stairs and railings. The main entrance has an original, single-light glass and wood door with the exterior porch entrance has a ca. 1980 sliding track door. The windows are original, one-over-one double hung wood sash and ca. 1980 one-over-one double hung vinyl sash. On the south façade is a two-story, projecting square bay with an exterior of aluminum siding and a solid wood door. There is a five-sided hipped roof tower dormer on the main façade roofline with one-over-one double hung vinyl sash windows. In the gable fields are multi-light fixed windows. On the basement level are original, three-light awning windows. On the north façade is a secondary entrance with an original, five-panel wood door.



At the rear of the dwelling is an original two-bay side gable roof garage with aluminum siding, two four-panel hinged double doors and a poured concrete foundation attached to a ca. 1950 one-bay garage. The one-bay garage has a concrete block foundation, aluminum siding, an original five-panel wood pedestrian door and an original thirty-panel and ten-light overhead track wood garage door. - **Contributing**



### 114 Applebee Street - Contributing

At this location is a one-story, gable front Craftsman dwelling built ca. 1920. The house has a poured concrete foundation, a front gable roof of asphalt shingles, an exterior end brick chimney and an exterior of vinyl siding. On the main (E) façade is a full-width, enclosed porch with tapered vinyl sided columns, four-over-one vertical wood windows and aluminum siding. The exterior door has an original three-over-one vertical-light double hung window and wood panel door flanked by two-light wood panel sidelights. In the gable fields are knee brace brackets and a three-light fixed window.

At the rear of the dwelling is a ca. 1970, one-bay garage with an exterior of aluminum siding and a ca. 1970 metal overhead track door. **Noncontributing**







### 118-120 Applebee Street - Contributing

At this location is a two-story, gabled ell Queen Anne influenced Folk dwelling built ca. 1885. The house has a continuous stucco foundation, a hip and gable roof of asphalt shingles, an interior central stone flue and an exterior of weatherboard siding. On the main (E) façade is an enclosed hipped roof entry with three-over-one vertical-light double hung wood windows, an exterior of weatherboard siding, wood stairs, wrought iron railings and a Craftsman-style, single-light glass and wood door. Also on the main façade is a square tower with a hipped roof and louvered vents, a stained glass diamond shaped window and a Craftsman-style, single-light window. On the south façade is a hipped roof dormer with a single-light window. On the southeast façade is a four-sided hipped roof bay with original, three-over-one vertical-light double hung wood sash windows on a wood base with vinyl siding, lattice and original Craftsman-style single-light windows. Other windows are original, three-over-one vertical-light and one-over-one double hung wood sash windows with wood surrounds.





### 130 Applebee Street - Contributing

At this location are two, two-story, dwellings built ca. 1900 and ca 1910. Both properties are contributing to the district. The north dwelling is a gable front Folk structure that appears to have been moved back from the street and angled in recent decades when the corner was reconfigured. The south house, a rectangular structure with a multi-gabled roof of asphalt shingles, has a continuous cut stone foundation, an interior brick flue and an exterior of weatherboard siding. On the main (E) façade is a hipped roof porch with a projecting gable, square wood posts, wood floor, wood baluster railing, tongue-in-groove ceiling and wood stairs, rails and brackets. The porch is supported by stone piers. The main entrance retains its original single-light glass and wood door. On the main façade is a large, single-light picture window flanked by thinner, single-light windows. On the south façade is a projecting hipped roof bay window with three, one-over-one double hung wood sash windows and an exterior of weatherboard siding. Also on the south facades is a hipped roof porch with a ca. 2000, six-panel metal door, an exterior of weatherboard siding, wood stairs and railing and supported by stone piers. Wood scaling and single-light fixed glass and wood windows decorate the gable fields.





Adjacent to the house on the north side is another ca. 1910 house which has been attached via a gable roof section with one-over-one double hung vinyl sash windows. The attached house has a front gable roof, a wood handicapped ramp on the northwest facade, an exterior of weatherboard siding, one-over-one double hung vinyl sash windows and a continuous rusticated concrete block foundation.

On the northeast façade is an hipped roof porch enclosed with a set of six, four-over-one vertical-light double hung wood sash windows, an exterior of weatherboard siding supported by a concrete block foundation. In the gable field on the northeast façade is an eight-light fixed window.





### **219 Applebee Street – Contributing (ARC Case 02-20)**

At this location is a two-story, rectangular American Foursquare dwelling built ca. 1910. The house has a continuous rock-faced concrete block foundation, a hipped roof of asphalt shingles, a central interior brick chimney and an exterior of aluminum siding. On the main (N) façade is a full-width, one-story, hipped roof porch enclosed with single panel screens set in wood frames and a wood screen door. The main entrance retains its original, single-light glass and wood door. The windows are primarily original, one-over-one double hung wood sash. A secondary entrance on the east elevation has a ca. 1980, flush wood door. At the roofline of the main façade is a shed roof dormer with paired, single-light fixed attic windows.

To the rear of the house is an original, frame, single-bay garage with a hipped roof of asphalt shingles, exposed roof rafters at the eaves, an exterior of horizontal board siding and paired vertical board hinged doors. - **Contributing**





### **223 Applebee Street - Contributing**

At this location is a one- and one-half story side-gabled Craftsman dwelling built ca. 1925. The house has a continuous poured concrete foundation, a side gable roof of asphalt shingles, an interior brick chimney and an exterior of vinyl siding. On the main (N) façade is a full-width, gable roof porch with square wood posts on tapered brick piers. The piers are connected by a closed railing of vinyl siding. The main entrance has a ca. 1990, nine-light glass and wood door. The windows in the dwelling are one-over-one double hung wood sash. The rear elevation has a shed roof dormer at the roofline and knee brace brackets are located at the eaves on both the house and porch. In the gable field of the porch are three, original, three-over-one vertical-light double hung wood sash windows.







### **227 Applebee Street - Contributing**

At this location is a one-and one-half story side-gabled Craftsman dwelling built ca. 1925. The house has a continuous poured concrete foundation, a side gable roof of asphalt shingles, an exterior brick chimney and an exterior of vinyl siding. On the main (N) façade is an incised porch enclosed with four-over-one vertical-light double hung wood sash windows. The central entrance to the porch has an original, nine-light glass and wood door with original, two-light glass and wood sidelights and an enclosed single-light transom. The main entrance has an original, four-vertical-light glass and wood Craftsman-style door. At the roofline of the main façade is a gable roof dormer with paired, three-over-one vertical-light double hung wood sash windows. The windows throughout the dwelling are original, three-over-one vertical-light double hung wood sash. A window on the east elevation, presumably the bathroom, is a rectangular, fifteen-light using glass builder's blocks for lights.

At the rear of the dwelling is an original, frame, two-bay garage with a hipped roof of asphalt



shingles, exposed roof rafters at the eaves, an exterior of weatherboard siding and two, ca. 1990, metal overhead track garage doors.  
- Contributing -

